



**TDC
GLASS**

technology | diversity | commitment

TDC GLASS

GEAMURI TERMOIZOLANTE

E-mail office@tdcglass.ro

Fax 0268 417 912 Tel. 0268 417 914

Mobil 0724 241 355

www.tdcglass.ro

QUALITY CERTIFICATE

Nr.80 /11.11.2020

We hereby certify, that the insulating glass units manufactured in our factory, as ordered by **SC. LACOLI CONSTRUCT S.R.L** through Invoice nr. **T07258/29.10.2020**, are complying with the requirements of the quality standards of the **European Regulations DIN 52460, DIN 18362 and EN 673**, with the following main characteristics of the product:

1. *Product traceability code:*

- #52 4 mm SATINDECO / 20 mm WE / 4 mm clar / 18 mm WE / 4 mm Low.E
- #52 4S 4 mm / 20 mm WE / 4 mm clar / 18 mm we / 4 mm Low.E

2. *Type, batch or serial number, that identifies the product in relation with the costumer request:*

- **Product label unique for each unit produced**

3. *Complete name, comercial or registred brand name and complete adress of the manufacturer:*

- **SC T.D.C-RO TELE DATA CONNECTORS SRL SRL, Str. Stejarilor, Nr.1 ,Brasov-Cristian, Romania, comenzi@tdcglass.ro**

4. *The present document is released for the structure mentioned at point 1, with the following components:*

- Glass sheet 1(outside) – **4 mm SATINDECO, 4 mm PLANITHERM 4S EVOLUTION ;**
– producer **SAINT GOBAIN GLASS**
- Glass sheet 2- **4 mm PLANICLEAR** -producer: **SAINT GOBAIN GLASS**
- Glass sheet 3 (inside)- **4 PLANITHERM XN** -producer **SAINT GOBAIN GLASS**
- Spacer -producer **PROFILCO**
- Molecular sieve(inside the spacer) : **VITRIMOL 3A**, producer **TEK-Metal**
- Primary sealing: **Butyl IGK 511**, producer **IGK**
- Secondary sealing: **Polyurethane IGK 130** , producer; **IGK**
- Inside neutral gas: **Argon, minim 90%**

5. *Thermal transmittance factor: :Ug=1.6; 0.8 W/m2K*

Manufacturing warranty:

The manufacturing warranty period, applies for a 24 months period, as stated in the European Directive 1999/44/EC and becomes effective from the delivery date.

Approved by Production Manager

Brasov:

T: + 40 268 417 914 | E: comenzi@tdcglass.ro

